

# Town of Edisto Beach



**W. Crawford Moore, Mayor**

**Administration**

Mark D. Aakhus, Town Administrator  
Donna Iskra, Municipal Clerk

**Council Members**

Jerome W. Kizer  
Robert Renner  
James R. Watts II  
Joey Bagwell

**Addendum 01**  
**Issued 8.27.2024**  
**2024-04 Construction Services at Jungle Road Park**

A simple handrail should be installed along the back side of the restroom facility where the boardwalk will begin ramping until it reaches the grade for the restroom sidewalk. Guards (pickets) are not necessary, but hand rails shall be continuous between runs. Materials should match the boardwalk. Example:



Framing materials were verified on site to be 4x4 posts imbedded in the ground with 2x8 stringers and a 2x6 walking surface. These materials are to be replicated on the newly constructed boardwalks. The approximately 18 feet of curbing should be removed and replicated. All fasteners should be stainless steel. Screws will be used for the walking surface and in any location subject to withdraw.



Where 4x4 posts are embedded in the ground, concrete is required. A minimum 12" diameter hole for each 4x4 post. Depth of posts shall be: 18" where boardwalk is level, 24" where the post support ramping for the boardwalk; backfill with concrete.

Where the current boardwalk ends and the new boardwalk is to begin and be connected, a “Y” shaped entrance is desired. The tail of the “Y” will be grade level for accessibility purposes. The below picture is not to scale but reflects the footprint.



There are approximately 4 information podium style stands that are set on 4x4 posts. These stands are to be replaced with new material. Stands with signs should have the signs removed and replaced on the new stands. The Town will remove and replace the signs, not the stands.

